

NICE 1000+

A simple and cost effective Integrated Solution for elevators to 1.5 m/s

Simplex and Duplex applications with closed loop geared and gearless PM machines

16 floors full collective using low cost conventional parallel wiring

Smooth Ride

- "Direct To Floor" technology, Waiting time optimises
- 4-Independent S-Ramps
- Default factory setting user friendly factory, gets you started quickly
- Anti-Rollback without any external load cell (Gearless Machine)
- Pre-torque function (Analog signal from load cell for Geared Machine)

Features Highlight

- Standard 8 Floors full collective, expansion option to 16 Floors **NEW** (Conventional Parallel Wiring)
- Maximum speed 1.5m/sec **NEW**
- Duplex onboard group control **NEW** (CANbus serial communication)
- Double digits 7-segment display **NEW** (Parallel connection)
- Selectable door control mode **NEW** (Manual, Semi-Auto, Auto)
- Selectable Fireman operation
- Synchronous (PM gearless Machine) or Asynchronous (Geared Machine)
- Single-Phase 220V UPS recue mode operation ready
- Comprehensive trip diagnostics
- Output frequency 0.0~100.0Hz
- High ambient temperature (45°C_{avg})

